VPS Contract Management
One Verizon Way
Basking Ridge, NJ 07920

SHORT TERM PUBLIC NOTICE UNDER RULE 51.333(a)

November 2, 2026

Carrier: Verizon Maryland LLC, 12 West Street, Annapolis, MD 21401

Contact: For additional information on these planned network changes, please contact:

Lisa M Thompson
Global Engineering and System Performance
Verizon Wireline Network Operations
13100 Columbia Pike
Silver Spring, MD 20904
(410) 375-9777

Michael Childs
Associate Director
Verizon Network Engineering
5055 North Point Pkwy
Alpharetta, GA 30022
(469) 497-4466

Implementation Date: On or after **December 30, 2026**

Planned Network Change(s) Will Occur at the Following Maryland Location(s):

Verizon Central Office	Address	CLLI
Arbutus MD DMS100 Switch	4505 Leeds Avenue Baltimore, MD 21229	**ARBTMDARDS0**
Annapolis MD C20 Switch	9 Northwest Street Annapolis, MD 21401	**ANNPMDANPS1**

This notice may also be viewed at:
http://www.verizon.com/about/terms-conditions/network-disclosures

PLEASE NOTE:

- All references to the Arbutus MD DMS100 switch are associated with CLLI code ARBTMDARDS0 and will not be repeated throughout the notice.
- All references to the Annapolis MD C20 switch are associated with CLLI code ANNPMDANPS1 and will not be repeated throughout the notice.

Description of the Planned Network Change(s):
The Verizon Arbutus MD DMS100 switch, located at 4504 Leeds Avenue, Baltimore, MD 21229, will be retired and removed from the Verizon network after all traffic served by this switch is migrated to the Annapolis MD C20 switch, located at 9 Northwest Street, Annapolis, MD 21401. All traffic to be migrated to the Annapolis MD C20 switch includes, but is not limited to, Inter-LATA (ACCESS/FG-B-D/CLEC IXC), wireless and paging traffic.

Description of Reasonably Foreseeable Impact(s) of the Planned Change(s):
All carriers—including competitive local exchange carriers (CLECs), Interexchange carriers (IXCs, IECs), wireless carriers, and paging carriers—will need to provision new trunk groups to support direct end office trunking to the Annapolis MD C20 switch or have existing trunk groups to that switch augmented.

All ASRs for the Annapolis MD C20 switch must be received no later than **December 1, 2026**, to provide sufficient time to migrate the traffic described above. Local Exchange Routing Guide (LERG) change effective dates will be posted prior to decommissioning of the Arbutus MD DMS100 switch (**on or after December 30, 2026**). This will serve to guide interconnect re-routes of traffic for the NPA codes currently served by the Arbutus MD DMS100 switch to reflect the Annapolis MD C20 switch as the new home switch. All trunks to the Annapolis MD C20 switch must be in place prior to the decommissioning of the Arbutus MD DMS100 switch.