

# **EXHIBIT 1**

A	B	C	D	E	F	G	H
Property No.	MDU Property Address	Municipality	MDU Owner (Landlord)	MDU Managing Agent Co.	Contact Name	Mailing Notes	Build Code*
7061502-1	192 BLEECKER ST	Manhattan	192 Bleeker Owners Corp.	Working Realty, Ltd.	Josh Prottas	Notices sent on 12/28/2015 & 02/19/2016	H
7061788-1	150 CENTRAL PARK S	Manhattan	150 Central Park South, Inc.		Patrick Lappin	Notices sent on 12/22/2015 & 02/03/2016	A
7061800-1	305 W 45 ST	Manhattan	I.G. Second Generation Partners, LP	Bldg Management Co., Inc.	Abraham Rosenbaum	Notices sent on 05/22/2013 & 12/13/2011	B
7064496-1	236 E 36 ST	Manhattan	Grossman Cedar Lane/36th Street, LLC	Bldg Management Co., Inc.	Abraham Rosenbaum	Notices sent on 03/21/2014 & 08/05/2014	A
8071951-1	23-05 30 AV	Queens	Cadre Astoria 23-05 30th LLC	Westminster Management	Kevin Schreiber	Notices sent on 12/22/2015 & 02/03/2016	A
8071956-1	23-15 30 AV	Queens	Cadre Astoria 23-15 30th LLC	Westminster Management	Kevin Schreiber	Notices sent on 12/22/2015 & 02/03/2016	A
8072262-1	34-02 32 ST	Queens	3406 32nd Street LLC	Lidia Management Corp.	Anthony Pistilli	Notices sent on 12/22/2015 & 02/03/2016	A
8073491-1	84-23 MANTON ST	Queens	Brian Owners, Inc.	David Associates	Cody Masino	Notices sent on 11/20/2015 & 02/03/2016	A
8086759-1	71 W 12 ST	Manhattan	71 West 12 Street LLC	Goldman Properties, Ltd.	James Giorgano	Notices sent on 01/25/2016 & 12/13/2011	A
8100106-1	406 E 161 ST	Bronx	Elton Parkview II Associates LLC	C&C Apartment Management LLC	Graciela Florimon	Notices sent on 11/08/2013 & 11/18/2013	A
8100391-1	840 GRAND CONC	Bronx	636 Holding Corp.	Role Realty Management Corp.	Ira Mack	Notices sent on 10/16/2014 & 10/02/2015	H
8100831-1	1209 NELSON AV	Bronx	Highbridge Heights Condominium	Impact Real Estate Management, Inc.	Carmen Martinez	Notices sent on 10/22/2015 & 02/03/2016	A
8101741-1	1090 CROES AV	Bronx	Croes Realty Corp.	Rettner Management Corp.	Ronald Rettner	Notices sent on 11/20/2015 & 12/10/2015	A
9405931-1	100 W 88 ST	Manhattan	100 West 88th Street HDFC		Carmen Burgos	Notices sent on 11/23/2015 & 12/10/2015	B
9406648-1	236 W 135 ST	Manhattan	Noha 135 Partners LLC	Heritage Realty, LLC	Edwin Shiraz	Notices sent on 01/11/2016 & 02/03/2016	A
13223946-1	34-20 32 ST	Queens	3420 32nd Street LLC	Lidia Management	Anthony Pistilli	Notices sent on 12/22/2015 & 02/03/2016	A
13277381-1	2539 W 15 ST	Brooklyn	The West Terrace Group Condominium		Jacob Ganzfried	Notices sent on 03/11/2015 & 02/03/2016	B

## LEGEND

### BUILD TYPES

#### **A Adhesive Fiber Cables**

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will be placed in 3-4" metallic conduit, which will be run through newly created holes drilled in the stairwell. 8" pull boxes will be established on the stairwell landing on each floor to house the pulled-through fiber cables. Where warranted, 20"x16"x8" lock boxes will be installed on the floor to house fiber distribution terminals. Horizontal fiber connections to each living unit ("drops") will be established with self-adhesive fiber cables. Small (4"x1.5"x.25") fiber termination boxes will be installed outside each living unit; the fiber drop will be extended into the living unit from this box at the time of installation. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

#### **B Existing Hallway Moldings**

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will be placed in 3-4" metallic conduit, which will be run through newly created holes drilled in the stairwell. 8" pull boxes will be established on the stairwell landing on each floor to house the pulled-through fiber cables. Where warranted, 20"x16"x8" lock boxes will be installed on the floor to house fiber distribution terminals. Horizontal fiber drops to each living unit will be provided via bundled drops utilizing the existing hallway molding infrastructure. Excess fiber cables ("slack") will be coiled in the molding in front of each living unit for penetration into the unit at the time of service order. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

#### **C Microducts and Access Panels**

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution

cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will be placed in 3-4" metallic conduit, which will be run through newly created holes drilled in the stairwell. 8" pull boxes will be established on the stairwell landing on each floor to house the pulled-through fiber cables. Where warranted, 20"x16"x8" lock boxes will be installed on the floor to house fiber distribution terminals. Horizontal fiber drops to each living unit will be provided via 12.7mm micro duct that are run through existing soffits or in the ceiling, to the front of each unit. Approximately 8"x8" access panels will be installed to enable penetration into the living unit at the time of service order. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

#### **D Microducts in Dropped Ceilings**

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will be placed in 3-4" metallic conduit, which will be run through newly created holes drilled in the stairwell. 8" pull boxes will be established on the stairwell landing on each floor to house the pulled-through fiber cables. Where warranted, 20"x16"x8" lock boxes will be installed on the floor to house fiber distribution terminals. Horizontal fiber drops to each living unit will be provided via 12.7mm micro duct that run through dropped ceilings; the fiber drops will be coiled close to each apartment. At the time of service order, penetration will be made into the living unit and a fiber drop will be pulled through the micro duct. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

#### **E Existing Conduit to Living Unit**

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will be placed in 3-4" metallic conduit, which will be run through newly created holes drilled in the stairwell. 8" pull boxes will be established on the stairwell landing on each floor to house the pulled-through fiber cables. Where warranted, 20"x16"x8" lock boxes will be installed on the floor to house fiber distribution terminals. Horizontal fiber drops to each living unit will be provided via existing building conduit, from the fiber distribution terminals directly into the living unit. At the time of service order, a fiber drop will be pulled through the conduit, possibly within a micro duct, where space allows. All Verizon work will be conducted in conformity with

the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

**F New Hallway Molding**

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will be placed in 3-4" metallic conduit, which will be run through newly created holes drilled in the stairwell. 8" pull boxes will be established on the stairwell landing on each floor to house the pulled-through fiber cables. Where warranted, 20"x16"x8" lock boxes will be installed on the floor to house fiber distribution terminals. Horizontal fiber drops will be placed in newly installed hallway molding running from the fiber distribution terminal to the end of the hallway on each floor. Extra slack will be left coiled in the molding in front of each unit for penetration into the unit at the time of service order. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

**G Fiber Drops Installed Directly into Unit from Riser**

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will be placed in 3-4" metallic conduit, which will be run through newly created holes drilled in the stairwell. 8" pull boxes will be established on the stairwell landing on each floor to house the pulled-through fiber cables. Where warranted, 20"x16"x8" lock boxes will be installed on the floor to house fiber distribution terminals. Fiber drops will be run directly into the living unit from the distribution terminal in the riser closet or stairwell. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

**H Exterior Bundled Drops**

4.8mm Indoor/Outdoor drop wires will be run vertically on the exterior of the building, passing closely by the window line for each set of stacked apartments in the building. The drop wires are attached to a metal cable that is fastened at the 1<sup>st</sup> floor level and at the rooftop level. Each wire is coiled outside the living unit it has been earmarked to serve. At the time of service order, the Verizon technician releases the coiled slack, drills a hole in the window sill and brings the drop wire into the unit. All Verizon work will be conducted in conformity with the property

work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

**I Multi-Customer Fiber Terminal**

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will run via 3-4" metallic conduit through either newly created core drills or existing vertical path in the communications/utility/media closets on designated floors. Verizon will mount Multi-Customer Fiber Terminals with average dimensions of 23"x19"x4" (wall mounted) or 84"x26"x15" (floor mounted). This terminal serves up to eight subscribers, with two (2) voice lines and one (1) data line each, and a common video jack. The units will be installed in the building's common utility area, using the existing copper wiring, CAT 5 and/or coax infrastructure to deliver service going to each living unit on serving floors. Building power needed to support MC-ONT design and battery backup is the responsibility of Verizon. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

**J In-Line Risers**

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more 12.7 mm micro ducts will be run through newly created holes drilled in closets within each living unit. A single 12.7 mm micro duct will terminate within each living unit resulting in a dedicated pathway between the living unit and the basement. At the time of service order, a fiber drop will be pulled through the micro duct. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.