

EXHIBIT 1

Property No.	Property ID	MDU Property Address	Municipality	No. of Living Units	MDU Owner (Landlord)	MDU Managing Agent Co.	Contact Person	Mailing Notes	Refusal Code*	Build Type*
1	8099381	1103 SHERIDAN AV	BRONX	52	1103-1105 Sheridan Ave. LLC	Park Avenue South Management	Maurice Mckenzie	Notices sent on 11/25/2013 & 01/21/2014	A	B
2	8100601	863 MELROSE AV	BRONX	54	Audubon HDFC	Arete Management LLC	Les Hansen	Notices sent on 08/19/2013 & 01/21/2014	P	A
3	8097170	10-11 NEILSON ST	QUEENS	60	1011 Neilson Realty LLC	Lilmor Management	Morris Lieberman	Notices sent on 11/25/2013 & 01/21/2014	A	A
4	7011272	302 E 88 ST	MANHATTAN	64	302 East 88th Street Tenants Corp.	Midboro Management	Adam Stern	Notices sent on 04/18/2013 & 01/21/2014	P	A
5	7067420	2440 OLINVILLE AV	BRONX	83	Olinville Realty LLC		David Radoncic	Notices sent on 12/03/2013 & 01/21/2014	P	A

LEGEND

REFUSAL CODE

A Active Refusal

P Passive Refusal

BUILD TYPES

A Adhesive Fiber Cables

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will be placed in 3-4" metallic conduit, which will be run through newly created holes drilled in the stairwell. 8" pull boxes will be established on the stairwell landing on each floor to house the pulled-through fiber cables. Where warranted, 20"x16"x8" lock boxes will be installed on the floor to house fiber distribution terminals. Horizontal fiber connections to each living unit ("drops") will be established with self-adhesive fiber cables. Small (4"x1.5"x.25") fiber termination boxes will be installed outside each living unit; the fiber drop will be extended into the living unit from this box at the time of installation. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

B Existing Hallway Moldings

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will be placed in 3-4" metallic conduit, which will be run through newly created holes drilled in the stairwell. 8" pull boxes will be established on the stairwell landing on each floor to house the pulled-through fiber cables. Where warranted, 20"x16"x8" lock boxes will be installed on the floor to house fiber distribution terminals. Horizontal fiber drops to each living unit will be provided via bundled drops utilizing the existing hallway molding infrastructure. Excess fiber cables ("slack") will be coiled in the molding in front of each living unit for penetration into the unit at the time of service order. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the

proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

C Microducts and Access Panels

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will be placed in 3-4" metallic conduit, which will be run through newly created holes drilled in the stairwell. 8" pull boxes will be established on the stairwell landing on each floor to house the pulled-through fiber cables. Where warranted, 20"x16"x8" lock boxes will be installed on the floor to house fiber distribution terminals. Horizontal fiber drops to each living unit will be provided via 12.7mm micro duct that are run through existing soffits or in the ceiling, to the front of each unit. Approximately 8"x8" access panels will be installed to enable penetration into the living unit at the time of service order. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

D Microducts in Dropped Ceilings

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will be placed in 3-4" metallic conduit, which will be run through newly created holes drilled in the stairwell. 8" pull boxes will be established on the stairwell landing on each floor to house the pulled-through fiber cables. Where warranted, 20"x16"x8" lock boxes will be installed on the floor to house fiber distribution terminals. Horizontal fiber drops to each living unit will be provided via 12.7mm micro duct that run through dropped ceilings; the fiber drops will be coiled close to each apartment. At the time of service order, penetration will be made into the living unit and a fiber drop will be pulled through the micro duct. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

E Existing Conduit to Living Unit

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser

path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will be placed in 3-4" metallic conduit, which will be run through newly created holes drilled in the stairwell. 8" pull boxes will be established on the stairwell landing on each floor to house the pulled-through fiber cables. Where warranted, 20"x16"x8" lock boxes will be installed on the floor to house fiber distribution terminals. Horizontal fiber drops to each living unit will be provided via existing building conduit, from the fiber distribution terminals directly into the living unit. At the time of service order, a fiber drop will be pulled through the conduit, possibly within a micro duct, where space allows. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

F New Hallway Molding

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will be placed in 3-4" metallic conduit, which will be run through newly created holes drilled in the stairwell. 8" pull boxes will be established on the stairwell landing on each floor to house the pulled-through fiber cables. Where warranted, 20"x16"x8" lock boxes will be installed on the floor to house fiber distribution terminals. Horizontal fiber drops will be placed in newly installed hallway molding running from the fiber distribution terminal to the end of the hallway on each floor. Extra slack will be left coiled in the molding in front of each unit for penetration into the unit at the time of service order. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

G Fiber Drops Installed Directly into Unit from Riser

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will be placed in 3-4" metallic conduit, which will be run through newly created holes drilled in the stairwell. 8" pull boxes will be established on the stairwell landing on each floor to house the pulled-through fiber cables. Where warranted, 20"x16"x8" lock boxes will be installed on the floor to house fiber distribution terminals. Fiber drops will be run directly into the living unit from the distribution terminal in the riser closet or stairwell. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

H Exterior Bundled Drops

4.8mm Indoor/Outdoor drop wires will be run vertically on the exterior of the building, passing closely by the window line for each set of stacked apartments in the building. The drop wires are attached to a metal cable that is fastened at the 1st floor level and at the rooftop level. Each wire is coiled outside the living unit it has been earmarked to serve. At the time of service order, the Verizon technician releases the coiled slack, drills a hole in the window sill and brings the drop wire into the unit. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.

I Multi-Customer Fiber Terminal

Verizon will install fiber optic feeder cable approximately .5" in diameter between a Verizon manhole in the street and the basement of the building, using existing entrance conduit. A fiber terminal (approximately 17"x20"x16") will be installed in the basement. Fiber distribution cables approximately .5" in diameter will be connected to the fiber terminal and will be run horizontally through the basement, using strand wire or 3-4" metallic conduit to a vertical riser path. Vertical risers consisting of one or more fiber cables approximately .5" or less in diameter will run via 3-4" metallic conduit through either newly created core drills or existing vertical path in the communications/utility/media closets on designated floors. Verizon will mount Multi-Customer Fiber Terminals with average dimensions of 23"x19"x4" (wall mounted) or 84"x26"x15" (floor mounted). This terminal serves up to eight subscribers, with two (2) voice lines and one (1) data line each, and a common video jack. The units will be installed in the building's common utility area, using the existing copper wiring, CAT 5 and/or coax infrastructure to deliver service going to each living unit on serving floors. Building power needed to support MC-ONT design and battery backup is the responsibility of Verizon. All Verizon work will be conducted in conformity with the property work requirements and with consideration for the safety of the residents and the proper functioning of the building. Impact to building aesthetics will be minimized by the use of materials smaller than those that typically serve the building at present.